

# DE-EE0009064 Integrated Mechanical System Pods (IMSPs)

Phius Presentation October 2022

Brett Webster, Galen Staengl

# Project Background

The business-as-usual approach to deep energy retrofits of multifamily buildings is **time-consuming disruptive**, **bespoke**, **and costly**, resulting in low retrofit rates ( $\sim 1\%/\text{yr}$ ), unrealized energy savings, and poor indoor living environments.

Prefabricated building envelope and packaged, multifunction mechanical system solutions represent an integrated retrofit package that could help unlock \$4.3 billion of annual energy savings in the multifamily sector just in ASHRAE climate zones 3, 4, and 5.





### **Research Questions**

- What are the integrated mechanical system prototypes that can best serve the market needs for targeted multifamily building typologies?
- What design and manufacturing approaches will allow these prototypes to commercialize and scale up quickly, adapt to a variety of existing conditions, easily integrate evolving technologies, and achieve cost compression necessary for widespread adoption?

# **Project Goals**

### Value Proposition

- Easy to install supports occupied retrofits
- Better occupant comfort
- Improved indoor air quality
- Opportunity for integration with panelized envelope systems
- Opportunity for cost compression at scale

### **IMSP-C**

- Designed for applications in buildings with central HVAC and DHW systems
- Targeting NE Midrise MF Building Typology

### IMSP-U

- Designed for applications where HVAC and DHW equipment is located in individual apartments
- Targeting CA Lowrise MF Building Typology

### Both prototypes will be

- all electric
- assembled with off-the-shelf components
- designed to be deployed in low-load applications driven by corresponding envelope improvements or mild climates

# **Project Team Roles**



RMI: Prime, management of grant and overall project strategy and vision



Staengl Engineering: Prototype design



TKF: Prototype fabrication, commercialization plan



**SCOE: Prototype testing** 



LBNL: Ventilation design advisor, test plan peer review



**AEA: CA typology & field advising** 

# Phase 1 Accomplishments

- Product Requirements
- Prototype Detailed Designs
- Building Conceptual Designs
- Controls Package
- Prototype Fabrication
- Testing
- Market Analysis and Commercialization Plan

# **Completed Prototypes!**





RMI – Energy. Transformed. IMSP-C IMSP-U

# IMSP-C

### **BUILDING TYPOLOGIES - NE MIDRISE**

### Typical mechanical systems for identified prototypical buildings

System	#1	#2	
# Units Represented	1,429,380	569,540	
% Units Represented	20.7%	8.3%	
Heating System	Steam or hot water system with radiators or pipes	Central furnace	
Heating Fuel	Piped NG	Piped NG	
Cooling System	Room AC	Central AC	
Water Heater in Apt?	No	Yes	

Source: RECS - New England, Mid-Atlantic, East North Central

System	NYC		Boston	
	20-49 units	50+ units	20-49 units	50+ units
Heating System	30% Furnace     60% Steam/hot water	• 35% Furnace • 49% Steam/hot water	• 46% Furnace • 30% Steam/hot water	• 59% Furnace • 17% Steam/hot water
Cooling System	<ul><li>16% Central AC</li><li>84% Room AC</li></ul>	<ul><li>31% Central AC</li><li>69% Room AC</li></ul>	<ul><li>43% Central AC</li><li>57% Room AC</li></ul>	<ul><li>69% Central AC</li><li>31% Room AC</li></ul>


Source: AHS

# **IMSP-C Prototype**





ERV with boost | Heating/Cooling | Economizer | Central DHW | Requires 1 30A, 115V connection plus central plant electrical

RMI - Energy. Transformed.





# IMSP-C 1-bd Apartment Layouts





# IMSP-C Studio, 2-bd Apartment Layouts





# IMSP-U

### **BUILDING TYPOLOGIES – CA LOWRISE**



762,018 Units

5-9 Units, 2 Stories: 70%

- Pre-1980: 60%
- 80s-90s: 30%
- Modern: 10%



647,511 Units

10-19 Units, 2 Stories: 70%

- Pre-1980: 60%
- 80s-90s: 30%
- Modern: 10%



629,470 Units

20-49 Units, 2-3 Stories: 79%

- Pre-1980: 62%
- 80s-90s: 27%
- Modern: 11%

Heating System	<ul> <li>Natural gas gravity wall furnace</li> <li>Central gas forced air furnace</li> </ul>	<ul> <li>Natural gas gravity wall furnace</li> <li>Central gas forced air furnace</li> </ul>	<ul> <li>Natural gas gravity wall furnace (rarer)</li> <li>Electric Resistance Wall Heater/Baseboard</li> <li>Central Steam/Hydronic Boiler w/radiator</li> </ul>
Cooling System	No cooling In-unit system	No cooling     In-unit system	<ul><li>No cooling</li><li>In-unit system</li></ul>
DHW System	In-unit non-condensing tank	In-unit/central non-condensing tank Central boiler	Central non-condensing tank     Central boiler

<sup>\*</sup> Data availability statewide was limited and this data is skewed towards Central Valley and Bay Area building types


# **IMSP-U Prototype**

**EPC 19-032 LG-MM Concept** 




All-in-one Unit


### **IMSP-U "Split Pod" Concept**



ERV | Heating/Cooling | Economizer | Fire smoke mode | DHW | Demand flex | Requires 1-2, 240V and 1 120V electrical connections

# IMSP-U Apartment Layouts





# Distribution Duct Concept – both products



- Phenolic ductwork with finish face (paintable) could eliminate the need for site-built soffits.
- Lightweight and insulated
- Easy to assemble on-site
- Multiple air pathways within one duct





RMI - Energy. Transformed.

# Test Setup



"Outdoor" Chamber Power Monitoring and Test Controls



Pod Water Supply



Airflow and Capacity Measurements

# **Strategic Pivot**

Team decision to prioritize IMSP-C for demonstration and commercialization efforts moving forward. Primary factors driving this decision:

- First costs
- Energy efficiency advantage
- Path to market
- Applicability of IMSP-C in both target geographies

### **BUILDING TYPOLOGIES – CA LOWRISE**



762,018 Units

5-9 Units, 2 Stories: 70%

- Pre-1980: 60%
- 80s-90s: 30%
- Modern: 10%



647,511 Units

10-19 Units, 2 Stories: 70%

- Pre-1980: 60%
- 80s-90s: 30%
- Modern: 10%



629,470 Units

20-49 Units, 2-3 Stories: 79%

\*\*\*\*\*\*\*\*\*\*\*\*\*

- Pre-1980: 62%
- 80s-90s: 27%
- Modern: 11%

Heating System	<ul> <li>Natural gas gravity wall furnace</li> <li>Central gas forced air furnace</li> </ul>	Natural gas gravity wall furnace     Central gas forced air furnace	<ul> <li>Natural gas gravity wall furnace (rarer)</li> <li>Electric Resistance         Wall Heater/Baseboard</li> <li>Central Steam/Hydronic         Boiler w/ radiator</li> </ul>
Cooling System	No cooling In-unit system	No cooling In-unit system	No cooling In-unit system
DHW System	In-unit non-condensing tank	<ul><li>In-unit/central non-condensing tank</li><li>Central boiler</li></ul>	<ul> <li>Central non-condensing tank</li> <li>Central boiler</li> </ul>

<sup>\*</sup> Data availability statewide was limited and this data is skewed towards Central Valley and Bay Area building types


# IMSP-C Retrofit Package
















### **DE-EE0009064**

A Recipe for ABC Multifamily Retrofits: Technologies, Financing, and Project Delivery

**ABC Phase 2** 

# Phase 1 Integration

9064
Integrated Mechanical System Pods




IMSP-C, Central Plant Concepts,
Prefabricated Ductwork

9062
Transforming Public Housing with
Deep Energy Retrofits



Integrated design and engineering, standardized solution, prefabricated panel, financing mechanism

9067
Streamlining BIM/CAD/CAM
Conversions for Panel Manufacturing



Improve scan to panel manufacturing workflow, 3D scanning to wireframe model creation



### Integrated Mechanical System Pod (IMSP)

### **TKFabricate**



Manufacturing, Commercialization

### **Staengl Engineering**



Design & Engineering

### Morben



Controls, User Interface

### **Optimized Thermal Systems**



Lab Testing, Field Validation

### **Envelope Panel**

### **Open Market ESCO**



Panel coordination with design team, contracting, digital workflow demonstration

### Signetron



Scanning to BIM/CAD/CAM

### **Panel Manufacturer**

IMSP & Panel Integration

### **Finance and Project Delivery**

### **Open Market ESCO**



Demonstration lead. Whole building retrofit design, financing and construction activities. Market scaling.

### M&V




### **Lawrence Berkeley National Lab**

Whole building retrofit M&V

# **Demonstrations**

# Demonstration Sites: 100% Low-Income Housing







# MA Demonstration: Walden Square Apartments



- 9-story midrise (120 units) + 5 lowrise complexes (120 units)
- 100% low-income apartments
- Owned and Managed by WinnCompanies

**Envelope** 

Min. Wall Insulation 30+ y/o windows

DHW

Central Condensing
Gas Boilers

Heating

Condensing Gas
Boiler Plant with
Hydronic Baseboard

Cooling

Window ACs

# MA Demonstration Retrofit Package

### **Envelope**

Scanning to BIM/CAD/CAM workflow

Prefabricated unitized retrofit panel

Mechanical

IMSP-C & Whalen Whispertherm

(Partial) Central plant upgrade

Prefabricated ductwork

### REALIZE-MA & Building America 8185 Industrialized Retrofit Envelope Specs

	<u> </u>	
Passive Measures	ASHRAE CZ 5A	ASHRAE CZ 4A
Wall R-value	R-32	R-27
Roof R-value	R-41	R-39
Basement/Ceiling R-value	R-22	R-13
Infiltration (cfm50 per sqft wall area)	0.08	0.08
Window	Whole window U-0.26, SHGC 0.41	Whole window U-0.26, SHGC 0.38

## CA Demonstration: Elizabeth Court



- 13 units, 2 stories
- 100% low-income rental housing
- Owned by Corporation for Better Housing (CBH)
- Managed by WinnCompanies

**Envelope** 

Min. Wall Insulation
Single Pane Windows

DHW

Central Gas Boiler
Plant

Heating

**Individual Furnaces** 

Cooling

**Window ACs** 

# CA Demonstration Retrofit Package

### **Envelope**

New Roof + insulation

High performance windows

Air sealing

Mechanical

**IMSP-C** 

Prefabricated ductwork


New central plant + new piping distribution

**GEBs** 

Thermal storage for demand flex


Solar PV

### **REALIZE-CA Retrofit Guidelines**



# **Achieving ABC Energy Saving Target**

# **MA Demonstration Prototype**





### CA Demonstration Prototype



<sup>\*</sup> Zero Over Time (ZOT): A phased decarbonization approach that optimizes retrofit investments at key trigger events in a building's lifecycle.

# **Operational Cost Savings**





# **Finished Product**

